BANGALORE DIVISION.

Notification dated 3rd February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 15th February 1936, for constructing a Traveller's Bungalow at Channapatna. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Travellers' Bungalow at Channapatna" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Approximate quantities required for the construction of a Travellers' Bungalow.

No.	Items of work	Per	Quantity	Rate as sanctioned	Rates	
					Words	Figures
				Rs. a. p.		
1	Earthwork excavation and filling in basement	C.yd.	83	0 3 9		
2	Burnt stone jelly concrete in lime mortar	C.ft.	729	0 3 9		
3	Burnt size stone in clay with bond stones for every 6 ft. in each course for foundation and basement ..	,,	1,708	0 3 6		
4	Burnt brick in clay ..	,,	1,397	0 3 6		
5	Burnt brick in mortar ..	,,	522	0 4 6		
6	Burnt stone slabs 6" thick one line dressed and fixed in mortar ..	S.ft.	673	0 6 0		
7	9" dr. stone pillars with base and capitals 8½' high nicely dressed ..	Each	10	30 0 0		
8	Burnt brick half pillars for the sides 8½' high with base and capitals ..	,,	2	5 0 0		
9	Rolled steel beams including hoisting, fixing, painting and boxing, etc., with fish plates, bolts and nuts ..	Cwt.	21·95	12 8 0		
10	Reinforced brick concrete terrace with 2 courses of flat tiles, etc., including plastering ceiling and top of terrace	Sqr.	14.90	70 0 0		
11	Mysore teak wood panelled doors 3½'×7½' and 2½'×6½' with iron clamps and fittings, etc., complete	S.ft.	191	1 12 9		

No.	Items of work	Per	Quantity	Rate as sanctioned	Rates	
					Words	Figures
				Rs. a. p.		
12	Mysore teak wood wall shelves 3′×5′ with 1″ thick cross planks and panelled shutters, etc., complete	S.ft.	30	1 4 0		
13	Mysore teak wood single shutter flap-doors with hinges, etc., complete	,,	30	1 8 0		
14	Mysore teak wood windows with shutters inside glazed, outside panelled with $\frac{3}{4}$″ diar. iron bars, clamps and fittings, etc., complete ..	,,	210	3 0 0		
15	Reinforced concrete perforated ventilators as per approved design ..	,,	48	0 12 0		
16	Burnt brick in mortar cornice as shown in plan including plastering and whitewashing, etc. ..	R.ft.	102	0 8 0		
17	Fleets all round the main building as shown on the plans ..	,,	135	0 4 0		
18	Burnt brick in mortar parapet wall 9″ thick and 2 ft. high including plastering, whitewashing, etc., complete as per plan ..	,,	248	0 8 0		
19	Plastering two coats with lime mortar	Sqr.	44.55	3 0 0		
20	Whitewashing, 2 coats ..	,,	45.00	0 3 9		
21	Cement pointing to basement ..	,,	3.44	3 4 0		
22	Silicate painting to doors and windows (grey colour) ..	,,	7.95	3 8 0		
23	Flooring with $1\frac{1}{2}$″ cement concrete on 3″ stone jelly lime concrete and plastered with $\frac{1}{2}$″ thick cement mortar mixed with red ocher including cutting squares, etc.	,,	12.24	25 0 0		
24	Providing sinks with brick in mortar and cement plastering ..	Each	2	10 0 0		
25	Providing and fixing teak wood pegs in the wall as shown on the plan ..	,,	12	0 8 0		
26	Providing and fixing 22 gauge 4″ dr. zinc sheet rain water down pipes ..	,,	12	1 0 0		
27	Providing and fixing ornamental cast iron railing 2′ high ..	R.ft.	30	2 0 0		
28	Providing and fixing expanded metal $\frac{3}{4}$″ mesh in teak wood frame with a doorway and silicate painting, etc., complete ..	S.ft.	100	0 14 0		

M. A. SRINIVASACHARI,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification dated 23rd—25th January 1936.

The attention of the public is invited to the notification published on page 133 of the *Mysore Gazette*, dated 30th January 1936, inviting tenders for the remaining maintenance work of Manchenahalli Tank, Register No. 69 of Goribidnur Taluk.

The last date for the receipt of tenders in this office is up to 2 P.M. on 15th February 1936.

N. SUBBA RAO,
Executive Engineer.